



**NOTE:**

CURB AND GUTTER SECTION SHALL BE REMOVED IN ACCORDANCE WITH DRIVEWAY WIDTH APPROVED BY THE CITY OF ASHEVILLE.  
 IF PERPENDICULAR CUT IS WITHIN 12" FROM A JOINT, THEN THE PARALLEL CUT SHALL BE MADE TO THAT JOINT.

REVISIONS	
DATE	DESCRIPTION



CITY OF ASHEVILLE, N.C.  
 ENGINEERING DEPARTMENT

STANDARD METHOD OF REMOVING EXISTING CURB  
 FOR A DRIVEWAY APRON INSTALLATION

STD. No.

3.12